

SEDE

Via Martelli, 26 - 40138 **Bologna**
Tel. (051) 534015 - Fax. (051) 530085

CERTI.CER.

LABORATORIO DI ZONA

Via Valle d'Aosta, 1 - 41049 **Sassuolo**
Tel. e Fax. (0536) 802154

Part. IVA 0094778-0375

Bologna, 17/04/2008

Spett. le
KERAPLAN S.r.l.
Via Scaldasole, 22/26
I-27020 DORNO - PV

TEST LABORATORY

TEST REPORT N° 3664/08

concerning ceramic slabs

(traslation of test report Nr. 3663/08 of 16/04/2008)

Requested by:	KERAPLAN S.r.l. Via Scaldasole, 22/26 I-27020 DORNO - PV
On (date):	21/03/2008
For the sample marked:	-----

The results reported relate only to the samples tested.

No responsibility is taken for the accuracy of the sampling unless it is done under our own supervision.

The reproduction of this test report is only authorized in the form of a complete photographic facsimile. Our written approval is necessary for any partial reproduction.

This test report consists of 3 pages this cover included.



Consorzio universitario per la gestione del
"Centro di ricerca e sperimentazione per
l'industria ceramica".
D.P.R. 10-4-1978 n. 806
(G.U. 20-12-1978 n. 353)

Laboratorio autorizzato ad effettuare il
servizio di rilevamento dell'inquinamento
atmosferico.
Decreto MINISTERO SANITÀ 10-8-1974
(G.U. 14-9-1974 n. 240)

Laboratorio iscritto nell'albo dei "Laboratori Esterni
Pubblici e Privati Altamente Qualificati".
Decreto MINISTERO RICERCA SCIENTIFICA 6-6-1983
(G.U. 6-7-1983 n. 183)

Membro ASTM
American Society for
Testing and Materials.

CENTRO CERAMICO - BOLOGNA

Test Report N° 3664/08 Date 17/04/2008

Page 2 of 3

DESCRIPTION OF THE SAMPLE: Glazed ceramic slabs 20 x 20 x 2.9 cm not marked.	
MANUFACTURER: KERAPLAN S.r.l.	
SAMPLING DETAILS: - Where: ----- - Date: ----- - By whom: CUSTOMER - How (methods): -----	
DATE OF RECEIVAL IN LABORATORY:	28/03/2008

TEST PERFORMED:

		Date of starting	Date of ending
<input checked="" type="checkbox"/>	ISO 10545 - 3 Determination of water absorption, apparent porosity, apparent relative density and bulk density	01/04/08	07/04/08

ISO 10545-3 - Determination of water absorption, apparent porosity, apparent relative density and bulk density**6.1 - BOILING METHOD**

Water absorption (%) of each slabs:

Sample	1	2	3	4	5
E(b)	3.9	3.3	3.5	3.8	3.4

E(b) Average (%):

3.6

Prof. Eng. Giorgio Timellini
DIRECTOR